LIST OF MACHINERY / EQUIPMENT / TOOLS

(For 1 MW Solar Energy System at Arcade Plaza)

1. Solar Panels & Frames

Sr. No.	Nomenclature of Panels	Quantity Nos.
1.	Number of Solar Panels (585W)	1710

2. Ducts/Cable Trays/Distribution Boxes

Sr. No.	Nomenclature of Ducts/Cable Trays	Quantity Feet
1.	Cable Trays 6x4"	100
2.	Cable Trays 8x4"	360
3.	Cable Trays 8"	09
4.	Cable Tray 6x4" to 8x4" Joint	01 (pcs)
5.	Cable Tray Bends 8x4"	05 (pcs)

3. AC/ DC Wires

Sr. No.	Nomenclature of DC Wires	Quantity Meters
1.	4mm Tin Cu XLPE/D/EVA DC Wire (Red)	11000
2.	4mm Tin Cu XLPE/D/EVA DC Wire (Black)	11000

Sr. No.	Nomenclature of AC Wires	Quantity Meters
1.	35mm 4-Core AC Wire	20
2.	4mm Cu PVC AC Wire (Earthing Wire)	270

4. Pipes/Elbows/Bends/Sockets

Sr. No.	Nomenclature of Pipes/Elbows/Bends/Sockets	Quantity Nos.
1.	PVC Pipes 4" (10')	20
2.	PVC Elbows 4" (10')	20
3.	PVC Bends 4" (10')	20
4.	PVC Sockets 3" (10')	0

5. Lightening Arrestors/Earthing Rods

Sr. No.	Nomenclature of Lightening Arrestors/Earthing Rods	Quantity Nos.
1.	Lightening Arrestors	06
2.	Earthing Rods	09

6. Protection Devices

Sr. No.	Nomenclature of Protection Devices	Quantity Nos.
1.	AC MCCB 200-250A	09
2.	DC Fuses 1000VDC	198
3.	DC SPD (Surge Protection Device)	99
4.	AC SPD (Surge Protection Device)	09

7. Distribution Boxes

Sr. No.	Nomenclature of Distribution Boxes	Quantity Nos.
1.	Distribution Boxes 4'x4'	09