LIST OF MACHINERY / EQUIPMENT / TOOLS

(For 70.76 KW Solar Energy System at Petrolium Exploration Ltd)

1. Solar Panels & Frames

Sr. No.	Nomenclature of Panels	Quantity Nos.
1.	Number of Solar Panels (585W)	122

2. Ducts/Cable Trays

Sr. No.	Nomenclature of Ducts/Cable Trays	Quantity Nos.
1.	PVC Ducts 80x80	04

3. AC/ DC Wires

Sr. No.	Nomenclature of DC Wires	Quantity Meters
1.	4mm Tin Cu XLPE/D/EVA DC Wire (Red)	500
2.	4mm Tin Cu XLPE/D/EVA DC Wire (Black)	500

Sr. No.	Nomenclature of AC Wires	Quantity Meters
1.	35mm 4-Core AC Wire	05
2.	4mm Cu PVC AC Wire (Earthing Wire)	30

4. Pipes/Elbows/Bends/Sockets

Sr. No.	Nomenclature of Pipes/Elbows/Bends/Sockets	Quantity Nos.
1.	PVC Pipes 4" (13')	08
2.	PVC Elbows 4"	10
3.	PVC Bends 4"	10
4.	PVC Sockets 4"	0

5. Pipes/Elbows/Bends/Sockets

Sr. No.	Nomenclature of Pipes/Elbows/Bends/Sockets	Quantity Nos.
1.	PVC Pipes 1" (10')	21
2.	PVC Elbows 1"	30
3.	PVC Bends 1"	30
4.	PVC Sockets 1"	0

6. Lightening Arrestors/Earthing Rods

Sr. No.	Nomenclature of Lightening Arrestors/Earthing Rods	Quantity Nos.
1.	Lightening Arrestors	01
2.	Earthing Rods	02

7. Protection Devices

Sr. No.	Nomenclature of Protection Devices	Quantity Nos.
1.	AC MCCB 200-250A	01
2.	DC Fuses 1000VDC	16
3.	DC SPD (Surge Protection Device)	08
4.	AC SPD (Surge Protection Device)	01

billsun
LET THE SUN PAY YOUR BILL

7. Distribution Boxes

Sr. No.	Nomenclature of Distribution Boxes	Quantity Nos.
1.	Distribution Boxes 18x24x6"	01