LIST OF MACHINERY / EQUIPMENT / TOOLS

(For 317 kW Solar Energy System at Printing Press Factory)

1. Solar Panels & Frames

Sr. No.	Nomenclature of Panels	Quantity Nos.
1.	Number of Solar Panels (610W)	520

2. Ducts/Cable Trays/Distribution Boxes

Sr. No.	Nomenclature of Ducts/Cable Trays	Quantity Feet
1.	Cable Trays 4"	100
2.	Cable Trays 6"	200
3.	Cable Trays 8"	40
4.	Cable Tray 4-6" Joint	01 (pcs)
5.	Cable Tray Bends 4"	10 (pcs)
6.	Cable Tray Bends 6"	08 (pcs)
7.	Cable Trays T shape 6"	08 (pcs)
8.	Cable Trays T shape 4"	08 (pcs)
9.	Cable Tray 6-8"Joint	01 (pcs)

3. AC/ DC Wires

Sr. No.	Nomenclature of DC Wires	Quantity Meters
1.	4mm Tin Cu XLPE/D/EVA DC Wire (Red)	2500
2.	4mm Tin Cu XLPE/D/EVA DC Wire (Black)	2500

Sr. No.	Nomenclature of AC Wires	Quantity Meters
1.	4-Core AC Wire	20
2.	4mm Cu PVC AC Wire (Earthing Wire)	370

4. Pipes/Elbows/Bends/Sockets

Sr. No.	Nomenclature of Pipes/Elbows/Bends/Sockets	Quantity Nos.
1.	PVC Pipes 3" (10')	40
2.	PVC Elbows 3" (10')	40
3.	PVC Bends 4" (10')	40
4.	PVC Sockets 3" (10')	10

5. Lightening Arrestors/Earthing Rods

Sr. No.	Nomenclature of Lightening Arrestors/Earthing Rods	Quantity Nos.
1.	Lightening Arrestors	04
2.	Earthing Rods	06

6. Protection Devices

Sr. No.	Nomenclature of Protection Devices	Quantity Nos.
1.	AC MCCB 225A 220/440V	02
2.	AC MCCB 225A 220/440V	01
3.	DC MCB 2P 63A 1000V	31
4.	DC SPD 2P 1000V/40kA(Surge Protection Device)	31
5.	AC SPD 275V/20kA(Surge Protection Device)	03

7. Distribution Boxes

Sr. No.	Nomenclature of Distribution Boxes	Quantity Nos.
1.	Distribution Boxes 4'x4'	01